

ADDENDUM #1
**COMPETITIVE BID #WG19-30 – Purchase & Installation of Four (4) Metal Buildings at
Various Baldwin County Highway Facility Locations for Baldwin County Commission**

This addendum consists of following changes:

All Barn Locations

- Pre-galvanized coating on secondary - Required
- 6" pedestal base on footers from floor elevation - Required
- 6" concrete base skirt on east and west side of barns for side sheet metal to overlap – Required

For Informational Purposes:

Baldwin County will paint primary and secondary members with county forces prior to installation.

Area 200

- Area 200 will have 16ft clearance height from base plate (including the portal frame) on north side (High Side)

Traffic/Sign

- Traffic/Sign will have 16ft clearance height from base plate (including the portal frame) on north side (High Side)

Area 300 (Barn)

- Area 300 will be a gable roof
- Area 300 will have 16 ft clearance height from base plate across entirety (including the portal frame)

Area 300 (Pump House)

- 6" concrete base skirt around pump house for sheet metal to overlap
- Roll up door is 9' wide x 7' tall
- 3070 standard metal door will be moved to south side of pump house and swing out.

Done this 25th day of March, 2019.



CHARLES F. GRUBER, Chairman
Baldwin County Commission